No. Serial	Items of work	Per	Rate	Quantity	Cost
			Rs. a. p.		
	Constructing a new relieving weir 15' in length.				
	Earthwork excavating hard gravelly soil	C. yd.		56	
	Burnt brick in surki mortar	C. ft.		321	
	Burnt stone slab 6" thick	S. ft.		76	
	Plastering with surki mortar	Sqr.		2·25	
	New rough stone work	C. yd.		75	
	Constructing a new cart bridge of one vent 3'×2'.				
	Earthwork	C. yd.		11	
	Burnt brick in surki mortar	C. ft.		590	
	Burnt brick in chunam	"		88	
	Burnt stone slabs 6" thick	S. ft.		147	
	Plastering with surki mortar	Sqr.		3·77	
	New rough stone work	C. yd.		21	
	Guard-stones	No.		4	
	Earthwork metalling and gravelling for road way ...	L. S.		...	

S. A. RAMASAMI IYER,
Executive Engineer.

GOVERNMENT OF MYSORE, ELECTRICAL DEPARTMENT.

Notice dated January 1918.

It is hereby notified for the information of the general public that certain old materials will be sold in public auction on Wednesdays and Saturdays near the Electrical Department, Old Stores, opposite to Messrs. Binny and Company and also in the Store yard behind the Chief Electrical Engineer's office. The sale will commence on Wednesday the 9th January 1918, between 1 P.M. and 5 P.M. near the old stores.

The material will be sold to the highest bidder who is required to deposit the sale amount immediately and before removing the material. The material should also be arranged to be removed immediately.

The undersigned reserves the right of rejecting any offer that may not seem to be reasonable to him.

Notice dated 20th December 1917.

Notice is hereby given that sealed tenders will be received at the Office of the Chief Electrical Engineer with the Government of Mysore, Bangalore, up to 26th January 1918, for constructing Power Station at the junction of Subedar Chattram and Race Course Roads, opposite to old Sowar Lines. The tender will be opened in public at 2 P.M. on Monday the 28th January 1918. The time required to complete the work should be indicated as this will be one of the chief factors in the award of the tenders.

2. The plans, detailed estimate and conditions may be obtained at the Chief Electrical Engineer's Office, Bangalore, between the hours of 11 A.M. and 5 P.M. on all working days.

3. Tenders should be submitted on printed forms which may be obtained from the Office of the Chief Electrical Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 1,500, in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Power Station at the junction of Subedar Chattram and Race Course Roads," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Government, which does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the award of the tender, the successful tenderer will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful tenderer will be posted on the notice board in the Chief Electrical Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The construction work should be started by the 15th February 1918.

Statement showing the approximate quantities of work for constructing a Power Sub-Station at the junction of Subedar Chattram and Race Course Road.

No.	Item of work	Rate Unit	Quantities, approximate
1	Earthwork, excavation and filling in basement	C. yd.	831
2	Concrete foundation	C. ft.	6,767
3	Stone in mortar, foundation and basement	"	10,111
4	Stone in mortar, superstructure	"	27,104
5	Stone slabs, 6" thick, exposed parts dressed	S. ft.	1,808
6	Cut-stone arch work	C.ft.	876
7	Quoire stones, 1" draft chiselling	"	708
8	Nicely dressed stone cornice, 6" deep	R. ft.	418
9	Brick cornice, 12" projection	"	385
10	Ornamental parapet wall	"	42
11	Cut-stone pillars with pedestals	No.	10
12	Ornamentation to basement windows	"	4
13	Cement pointing	Sqr.	353·78
14	Mangalore tile flooring on 3" concrete	"	48·55
15	Madras terrace roofing	"	1·69
16	Cement concrete arches on I beams and Mangalore tile flooring	"	42·78
17	Teakwood flooring, 1½" tongued and grooved	"	9·63
18	Mangalore tile roofing on galvanized corrugated iron sheeting	"	77·10
19	Ridge tiles set in mortar	R. ft.	202
20	Zinc sheeting to valleys	"	116
21	Ornamental eave guttering fixed, complete	"	246
22	Cast iron pillars, 11 ft. long	No.	8
23	W. I. trusses, 36 and 31 ft. clear span	"	14
24	Hoisting charges, etc., for the above trusses	"	14
25	W. I. work fixed, complete	Cwt.	262·37
26	Bolts and nuts, etc.	"	·5
27	W. I. pipe railings to galleries	R. ft.	225
28	Teakwood work with wood oiling	C.ft.	822·93
29	Teakwood panelled and glazed doors	S. ft.	479
30	Teakwood glazed windows	"	1,433
31	T. W. circular and semi-circular windows	"	29
32	Painting with 3 coats of silicate paint	Sqr.	150·56
33	Pressed brick in cement	C.ft.	133
34	Cement concrete slabs, 2" thick	"	210
35	Wire gauge shutters	S. ft.	807
36	Fifty lbs. rail to travelling crane	R. ft.	200
37	Galvanized iron rain water down pipes, 4" diameter	"	700

S. G. FORBES,
Chief Electrical Engineer to the Government of Mysore.

BANGALORE DIVISION.

Abstract Notification, dated 4th January 1918.

Attention is invited to the notice calling for tenders for opening out a new road from Kengeri to Tavarekere, published in Part IV of *Mysore Gazette*, dated the 3rd January 1918.

Attention is invited to the notification published in Part IV of the *Mysore Gazette*, dated the 10th January 1918, calling for tenders for gunny bags required for constructing a new Maralvadi Tank at Kankanhalli.

C. VIJAYARANGAM NAIDU,
Executive Engineer.

MYSORE DIVISION.

Notice dated 4th January 1918.

AUCTION SALE OF RATTAN MATS.

1. Notice is hereby given that rattan mats used for the flooring at the Public Offices, Mysore, (approximate quantity 13,000 square feet) will be sold in public auction commencing at 8 A.M., on Sunday the 27th January 1918.

2. The mats will have to be removed from the different office blocks by the approved bidder. The auction will be conducted by the Executive Engineer or by some other officer deputed by him for the purpose.

3. The mats can be inspected during office hours in the several office blocks of the Public office buildings at Mysore.

4. One-fourth of the purchase money should be paid at the time of auction and the remaining before the removal of materials.

N. B.—It may be noted that there is a Government bidding of three pies per square foot already.

Notice dated 17th December 1917.

Attention of the public is invited to the advertisement in detail published in the *Mysore Gazette*, dated 3rd January 1918, calling for tenders for improving the roads at Karapur Camping grounds.

Y. ASWATHANARAYANA RAO,
Executive Engineer.